

RP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name United Producing Co. Inc.

Complete Address: Box 946 Liberal, Kansas

Lease Name A.H. Lehman Well No. # 1

Location C NW SE Sec. 21 Twp. 29 Rge. (E) (W) 34

County Haskell Total Depth 5503'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Gayle E. Toland

Address: Okla. City, Okla. License No. 246

Operation Completed: Hour 3 PM Day 19 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 1821' Circulated w/cement. 5 1/2" 5502' Cemented.

Plug back-5290' Top Perforations-5055'

Sand 5290' to 5000' 5 sax.cement 5000' to 4975'

Mud 4975' to 650' Plug and 30 sax.cement 650' to 550'

Mud 550' to 50' Rock Bridge 50' to 40'

15 sax.cement 40' to surface. Weld cap on surface.

Company Pump. Pulled 1775' 5 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Alfred Scott*
Well Plugging Supervisor

DATE 12-26-62

INV. NO. 6285-W