

MP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Hinks Petroleum Co., Inc., c/o Gabbert-Jones, Inc.

Complete Address: 514 Orpheum Bldg., Wichita, Kansas

Lease Name Thomas Well No. # 1

Location C SW SE Sec. 22 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4327'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 6:30 PM Day 5th Month May Year 1965

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cement circulated. Drilling mud from the
pits was pumped into the hole. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 200', and cemented with 25 sacks, through the
drill pipe. Fluid in the hole was now at 30', 2nd cementing plug,
bridged solid with hulls on fluid at 30', and cemented with 8 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/7/65

INV. NO. 1119-W