

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co

Complete Address 217 N Water Wichita, KS

Lease Name Crumley Estate Well No. 2

Location 150' S/G/W/2/NW/NE Sec. 22 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4285

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 10:00 AM Day 17 Month 1 Year 1974

The above well was plugged as follows:

258 ft 8 5/8 surface cemented with 200 sacks. 4283 ft 5 1/2 long string  
cemented with 100 sacks. Top perf. 4214 ft. Sand to 4200 ft. 5  
sacks cement with bailer. Pulled 3700 ft 5 1/2. Set 10 ft rock bridge  
at 200 ft. 25 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10  
sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/22/74

INV. NO. 8426-W