

*V*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co.

Complete Address 217 N. Water Wichita, Ks

Lease Name Vanlandingham Well No. 2-D

Location SE/NE/NW Sec. 22 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4375

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 4:00 PM Day 22 Month 6 Year 1972

The above well was plugged as follows:

268 ft 8 5/8 surface pipe cemented with 200 sacks. 4274 ft 5 1/2 long  
string cemented with 100 sacks. Top perf. 4200 ft. Sand back to  
4175 ft, 5 sacks cement with bailer. Pulled 3585 ft 5 1/2. Set 10 ft  
rock bridge at 265 ft. Fill hole with 4 1/2 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: L. Russell Bibeault  
Well Plugging Supervisor

INVOICED

DATE 6/29/72  
INV. NO. 5939-W