

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-095-21085-0000

LEASE NAME Vanlandingham

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
 SE NW SE

SEC. 21 TWP. 30 RGE. 7W (E) or (W)

COUNTY Kingman

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400
 Wichita, Kansas 67202

PHONE# (316) 263-8267 OPERATORS LICENSE NO. 5427

Date Well Completed

Character of Well Gas

Plugging Commenced 6-8-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-17-88

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #2 Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	302'	none
				5-1/2"	4346'	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped bottom with 50 sacks cement to 4100'. Shot pipe @3800', 3720', 3600', 3500', pulled a total of 87 joints of 5-1/2" casing. Plugged surface with 3 hulls, 20 gel, 1 hull, 8-5/8" plug, 120 cement, 60/40 pos., 2% gel. Plugging Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050-FIVEN

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

JUN 27 6-27-88

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*
 (Address) Box 347
Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 88

Irene Hoover
 Notary Public

My Commission Expires: 