

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Co.

Complete Address 2915 N. Lincoln Oklahoma City, OK

Lease Name James G. Schuman Well No. 2

Location SW/NW/NW Sec. 20 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4376

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 6 Month 11 Year 1972

The above well was plugged as follows:

260 ft 9 5/8 surface pipe cemented with 200 sacks. 4375 ft 5 1/2 long
string cemented with 150 sacks. Top perf. 4218 ft. Sand to 4200 ft.
5 sacks cement with bailer. Pulled 3600 ft 5 1/2. Set 10 ft rock
bridge at 260 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 11/8/72
INV. NO. 6599-W