

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed June 30, 1967.

Dear Sir:

Mr. Paul Lacey of Beardmore Drilling Co. has this  
date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name: Wagner Unit Well No. # 1

Location: SW SW Sec. 35 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5108' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

445' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill  
hole with drilling mud to 360', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1967

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Archie Elving  
Conservation Division Agent