

State of Kansas



FORM - CP-2

P

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Glen of Glen and Smith has this

date requested permission to plug the following described well:

Mr. Ralph Glen guarantees payment of the plugging fee.

Operator's full Name: Champlin Oil and Refining Co.

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name: Georgia Eubank Well No. # 1

Location: C NW 1/4 Sec 28 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5205 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Glen was instructed to plug the well as follows:

5193' of 4 1/2" long string cemented with 50 sacks. Plugged back
5150'. Top of perforation 5135'. Sanded to 5125' cemented with
3 sacks. 665' of 8 5/8" surface pipe cemented with 300 sacks.
Fill hole with mud to 200'. 10' rock bridge cemented with 20
sacks. Fill with mud to 40'. 10' rock bridge cemented with 10
sacks to base of cellar.

Very truly yours,

Archie Elving
Conservation Division Agent