

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL, Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 5 1965

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Carter & Mandel Company

Complete Address: 904 Lubbock National Bank Bldg., Lubbock, Texas

Lease Name: Kelly Well No. # 1

Location: C NE SE Sec. 10 Twp. 29 Rge. 19 (E) (W) W

County Kiowa Total Depth 5055' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

660' of 8 5/8" surface pipe. cement circulated with 400 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat & mouse holes with  
5 sacks.

Very truly yours,

*Archie Elving*