

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Leon Boughner of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Boughner guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 W. Douglas, Wichita, Kansas

Lease Name: Dargel "B" Well No. # 1

Location: C NE SW Sec 15 Twp. 29 Rge. 18 (E) (W) W

County Kiowa Total Depth 5048' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Boughner was instructed to plug the well as follows:

462' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat and mouse hole with 4 sacks

Very truly yours,

Archie Elving  
Conservation Division Agent