



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

RECEIVED
STATE CORPORATION COMMISSION

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
Colorado Derby Building
WICHITA, KANSAS 67202
27-November 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Sargants of Sargants Casing pulling service has this date requested permission to plug the following described well:

Operator's Full Name: Nelson Enterprise

Complete Address: 1675 Broadway Suite 2770 Denver Colo. 80202

Lease Name: Dargel Well No. 1

Location: C-NE-SE Sec. 9 Twp. 29S Rge. 18W (E) (W)

County: Kiowa Total Depth: 5047'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: This well was completed & tested but not produced

Mr. Sargant was instructed to plug the well as follows:

There is 450' of 8 1/2" surface casing cement circulated. There is 5047' of 4 1/2" production pipe cemented to 4200'. The perforations are from 4510' to 4516'. They had plugged this well back to 4900'. 1st plug 1 sbx of hulls + 20 sbx of cement to bottom. 2nd plug on solid bridge at 1200' with 35 sbx of cement. 3rd plug on solid bridge at 460' with 35 sbx of cement. 4th plug 40' to 0' on solid bridge with 10 sbx of cement. Plugging accomplished by Sargants casing pulling service.

Recovered 3416' of 4 1/2" production pipe

Very truly yours,

Paul Luthie
Conservation Division Agent