



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

15-April-1982

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-097-20,873-0000

Dear Sir:

Mr. Marvin Julian of Murphy Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Raymond Oil Co. Inc.  
Complete Address: One Main Place Suite 900, Wichita, Kansas 67202  
Lease Name: Chisad Well No. 1  
Location: C-5/2-NW/4 Sec. 5 Twp. 29 Rge. 19 (E) (W)  
County: Nowata Total Depth: 5050  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereafter indicated: \_\_\_\_\_

Mr. Julian was instructed to plug the well as follows:

They have 650' of 8 3/8" surface casing cement circulated. The anhydrite was topped at 1290'. 1st plug 1210' with 60 sbs of cement. 2nd plug push rubber plug to 620' with 35 sbs of cement pumped on top of it. 3rd plug 40'to 0' on solid bridge with 10 sbs of cement. Then circulated 10 sbs of cement in rat hole & 5 sbs of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by allied cementing.

Very truly yours,

Paul A. Luthi  
Conservation Division Agent