



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

22 - September 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-097-~~2806~~-0000

20806

Dear Sir:

Mr. Mike Sharp of Trans-Pack Drilling has this date requested permission to plug the following described well:

Operator's Full Name: Midea Exploration Inc.

Complete Address: 411 Farmers Bankers Building 200 East 1st Wichita Kansas 67202

Lease Name: Berney Well No. 1

Location: C-NE NW Sec. 16 Twp. 29 Rge. 20W (E) (W)

County: Kiowa Total Depth: 5250

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Sharp was instructed to plug the well as follows:

*There is 616' surface casing cement circulated. 1st plug with hole full of heavy mud circulated at 1750' for 10-min then pumped 5 cbls of cement to 1750'. 2nd plug pushed rubber plug to 600' and put 1 sbx of hulls + 35 sbx of cement on rubber plug. 3rd plug on solid bridge at 40' to 0' with 1/2 sbx hulls + 10 sbx of cement. They also pump 5 sbx of cement in rat hole + 5 sbx of cement in mouse hole. There was a water well drilled on land owner wanted it left. They were advised to make a legal written authority + file it with Corporation Com. Plugging accomplished by Allied Cementing about of Great Bend, KS. There was a water well + Mr. Berney was to sign papers to Key well.*

*Very truly yours,*  
Paul Luthers  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

SEP 28 1981