

RECEIVED

OCT 11 2002

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-08121144-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Chesapeake Operating, Inc. KCC LICENSE # 32334  
(owner/company name) (operator's)  
ADDRESS P. O. Box 18496 CITY Oklahoma City, OK 73154-0496

STATE OK ZIP CODE 73154-0496 CONTACT PHONE # (409) 848-8000

LEASE MLP Collingwood WELL# 1-8 SEC. 8 T. 29S R. 34W (East/West)  
- C - SE - NE SPOT LOCATION/0000 COUNTY Haskell

1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8 SET AT 1781' CEMENTED WITH 650 SACKS

PRODUCTION CASING SIZE 5 8-1/2 SET AT 5626' CEMENTED WITH 350 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4079-4484'

ELEVATION KB 3007' T.D. 5630' PBTD - ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CTBP @ ±4050' & cap w/20' cmt, displace hole w/9 ppg & 36 viscosity mud to ± 1831', cut off csg @ ±1781' & set 100' cmt plug from 1831-1731', Displace surf csg w/9 ppg & 36 vis. mud & cap w/50' cmt

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bud Neff PHONE# ( ) (620) 377-0803

ADDRESS 4532 W. Jones Ave. City/State Garden City, KS -7846

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # 99996  
(company name) (contractor's)

ADDRESS P. O. Box 31, Russell, KS PHONE # ( ) \_\_\_\_\_

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10/08/02 AUTHORIZED OPERATOR/AGENT: Randy Gasaway  
Randy Gasaway (signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Chesapeake Operating, Inc.  
PO Box 18496  
6200 N Western Ave.  
Oklahoma City, OK 73154-0496

October 15, 2002

Re: MLP COLLINGWOOD #1-8  
API 15-081-21144-00-00  
SENE 8-29S-34W, 1980 FNL 660 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888