

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 18 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 367, Great Bend, Kansas

Lease Name: Dauner Well No. # 1

Location: 2310 FNL & 330 FWL Sec. 21 Twp. 29 Rge. 12 (E) (W) W

County Pratt Total Depth 4720 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

253' of 13 3/8" surface pipe, cement circulated.

Fill hole with mud to 250', 1st cementing plug, 1/4 sack

hulls, cement with 30 sacks. Fill hole with mud to 40',

2nd cementing plug, 1/4 sack hulls, cement with 20 sacks to

base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent