

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1966

Conservation Division
Wichita, Kansas

7-14-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ipson of Ashland Oil & Refin. Co. has this
date requested permission to plug the following described well:

Mr. Ipson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Okla.

Lease Name: G. Koenig Well No. 4

Location: NW SE Sec. 28 Twp. 29 Rge. 34 XX (E) (W)

County Haskell Total Depth 5501' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ipson was instructed to plug the well as follows:

8 5/8" to 1827' circulated w/ cement. 5 1/2" to 5493' cemented.

Top perforations 5243' Plug bottom w/ 20 sacks cement.

Top of cement 5050' Mud 5050' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eeles
Conservation Division Agent