

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 7 TWP. 28S RGE. 13 E/W
Location as in quarters or footage from lines:
C. SE. NW

	+		

Locate Well
correctly on above
Section Platt.

Lease Owner Texas Energies, Inc.
Lease Name Harris Well No. 1-7
Office Address Box 947 Pratt, KS 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 8-29-81
Application for plugging filed _____
Plugging commenced 8-29-81
Plugging completed 8-30-81
Reason for abandonment of well or producing formation _____

Non-productive (Dry)
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation -- Depth to top -- bottom -- T.D. --

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	349'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

Plug to abandon w/135 sxs 50/50 poz cm; 3% cc 4% gel. Fill hole
with heavy mud-60 sxs @ 640'; 50 sxs @ 320' 10 sxs @ 40'; 10 sx
rathole; 5 sxs waterwell.

10-28-81

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Texplor CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas COUNTY OF Pratt, ss.
Larry R. Belding (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) [Signature]
Box 947 Pratt, KS 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of Oct., 19 81

Retha Buettgenbach
Notary Public.

My Commission expires: 5-18-82

RETHA BUETTGENBACH
STATE NOTARY PUBLIC
PRATT COUNTY, KANSAS
MY APPT. EXPIRES 5-18-82



15-151-20917-0000

TEXAS ENERGIES, INC.

DRILLERS' WELL LOG

Harris #1-7
C SE NW, Section 7, T28S, R13W
Pratt County, Kansas

Commenced: 8-16-81

Completed: 8-29-81

Operator: Texas Energies, Inc.

FROM	DEPTH TO	FORMATION	REMARKS
0	350	Sand & Redbeds	Spudded @ 3:00 8-16-81
340	1040	Sand & Shale	Drilled hole to 349' set 338' of
1040	1917	Lime & Shale	used 8 5/8" 28#/ft pipe w/125 sx
1917	2523	Lime & Shale	Light w/3% cc tailed in w/150 sxs
2523	3032	Lime & Shale	common 3% cc 2% gel
3032	3240	Lime & Shale	Plug down @ 9:00 p.m.
3240	3468	Lime & Shale	
3468	3684	Lime & Shale	Total depth 4589'
3684	4028	Lime & Shale	Plugged with 135 50/50 poz sxs
4028	4183	Lime & Shale	as follows: 60 sx @ 640', 50 sx
4183	4368	Chert & Lime	@320', 10 sx @ 40', 10 sx rathole
4368	4589	Arbuckle	5 sxs water well.

Job completed @ 2200 8-29-81.

STATE OF KANSAS)
) ss.
COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RECEIVED
STATE CORPORATION COMMISSION

TEXAS ENERGIES EXPLORATION CO. INC. 28-1981

CONSERVATION DIVISION
Wichita, Kansas

BY: E. R. Belding
E. R. Belding, Vice-President

My Commission Expires:

5-18-82

Retha Buettgenbach
Notary Public

RETHA BUETTGENBACH
STATE NOTARY PUBLIC
PRATT COUNTY, KANSAS
MY APPT. EXPIRES 5-18-82

MY APPT. EXPIRES
PRATT COUNTY, KANSAS
STATE NOTARY PUBLIC
RETHA BUETTGENBACH