

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 2 TWP. 28S RGE. 13W E/W
Location as in quarters or footage from lines:
NW SW SW

Lease Owner Woolsey Petroleum Corporation
Lease Name Black Well No. 1
Office Address Suite 400, 300 W. Douglas, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed August 19, 1981
Application for plugging filed August 19, 1981
Plugging commenced August 19, 1981
Plugging completed August 19, 1981
Reason for abandonment of well or producing formation DRY HOLE

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Morris Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 4,361'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	128'	
				8-5/8"	1,027'	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Mud to 1,000', 40 sx cement
Mud to 500', 35 sx cement
Mud to 40', plug 1/4 sx hole
10 sx cement, 10 sx cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1981
CONSERVATION DIVISION
Wichita Kansas


8-24-81

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Donald E. Hunt (employee of owner) or ~~(owner/operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Donald E. Hunt
Suite 250, 200 W. Douglas, Wichita, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 1981



Sue Anne Kelley
Sue Anne Kelley Notary Public.

15-151-20959-0000

DRILLERS LOG

#1 BLACK
 NW SW SW Section 2-28S-13W
 Pratt County, Kansas

OPERATOR: WOOLSEY PETROLEUM CORPORATION
 Suite 400, 300 West Douglas
 Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

COMMENCED: July 30, 1981

COMPLETED: August 18, 1981

CASING RECORD: 10-3/4" @ 128' w/1,165 sx
 8-5/8" @ 1,027' w/300 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	550	Sand, shale and shells
550	1040	Shale and sand
1040	1365	Shale and limestone
1365	1530	Shale
1530	3042	Shale and lime
3042	3090	Lime
3090	3830	Lime and shale
3830	3953	Lime
3953	4009	Limestone and shale
4009	4014	Lime
4014	4085	Limestone and shale
4085	4250	Lime
4250	4361	Lime and shale
4361		Rotary total depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1981
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt
 Donald E. Hunt

Subscribed and sworn to before me this 21st day of August, 1981.

My appointment expires:
 July 16, 1985

Sue Anne Kelly
 Notary Public

