

15-095-20189-0000


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Kingman County. Sec. 13 Twp. 28S Rge. ~~22~~ 9 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW  
Lease Owner Pickrell Drilling Company  
Lease Name Schwartz "C" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 29 19 69  
Application for plugging filed November 29 19 69  
Application for plugging approved November 29 19 69  
Plugging commenced November 29 19 69  
Plugging completed November 29 19 69  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 4093 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 200' w/25 sacks cement  
Top Plug @ 40' w/15 sacks cement

12-17-69  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.



(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 8th day of December, 19 69

L. M. Whiting  
Notary Public.

My commission expires May 10, 1970

**ROTARY DRILLING LOG**

15-095-20189-0000

**COMPANY:** Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 11/20/69

Rotary Drilling Completed 11/29/69

**LOCATION:** Schwartz "C" 1, NE NE SW Section 13-28S-9W  
Kingman County, Kansas

**CONTRACTOR:** **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

**CASING RECORD:** Run 10 Jts. 28# 8-5/8" surface casing set at 206' KB. Cemented with 170 sacks. Completed 8:45 PM November 20, 1969. Circulated.

No oil string run. D & A Plugged 9:00 AM November 29, 1969

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

20	Sand	<u>C.F.S.</u>
206	Red Rock	3275
345	Red Bed & Shale	3360
1245	Shale	3380
2010	Shale & Lime	3405
2050	Lime & Shale	3444
2960	Shale & Lime	3790
3010	Shale	3805
3133	Shale & Lime	3840
3490	Sandy Lime & Shale	3851
3649	Lime	4083
3868	Lime & Shale	4093
3912	Shale & Lime	
4055	Lime & Shale	
4072	Shale & Lime	<u>S.L.M.:</u>
4093	Miss. Chert, RTD	Board 3455.54
		Strap 3454.71
		.83 Difference
		<u>Slope Tests:</u>
		2000
		2500
		3000
		3500
		4000

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 8th day of December, 1969, before me the undersigned, a Notary Public, in and for the County of Sedgwick State of Kansas, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Witness my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]  
L. M. Whiting Notary Public