

15-099-10068 0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman

County. Sec. 30 Twp. 28 Rge. 9(W)

Location as "NE/CNW/SW" or footage from lines. SW SE SE

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Alexander Well No. 1

Office Address 301 South Broadway Wichita 2 Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed Jan. 6 19 53

Application for plugging filed Jan. 6 19 53

Application for plugging approved Jan. 6 19 53

Plugging commenced Jan. 6 19 53

Plugging completed Jan. 6 19 53

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives

Producing formation Depth to top Bottom Total Depth of Well 1640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
sand & clay	dry	0	40			
shale	dry	40	50			
sand	water	50	75			
shale & shells	dry	75	226	8 5/8	226	cemented with 150 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 1640 - 226  
 wood plug 226 - 223  
 cement 223 - 195  
 mud 175 - 15  
 wood plug 15 - 12  
 cement 12 - bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1953

1-13-53

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. R. Lauck Oil Company, Inc.

Address 301 South Broadway Wichita 2 Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James F. Ralstin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James F. Ralstin

Wichita Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12 day of January, 19 53

My commission expires Sept. 14, 1955

Elizabeth Gay Notary Public

24-2675-S 2-52-20M

PLUGGING  
FILE SEC 30 T 28 R 924  
BOOK PAGE 71 1953

15-09510068-0000

D. R. Lauck Oil Company, Inc.

Alexander #1 SW SE SE 30-28S-9W.  
Kingman County Kansas

Commenced: Dec. 17, 1952  
Completed: Jan. 6, 1953

TD 4640 226' 8 5/8" casing cemented with  
150 sacks

Elevation: 1722 DF  
1724 KB

Sand & clay	40
shale	50
sand	75
shale & shells	226
shale & red bed	1110
shale & shells	1230
Anhydrite	1255
shale & shells	1362
shale & lime	1975
lime & shale	2165
shale & lime	2989
lime	3405
lime & shale	3485
lime	3890
lime & shale	3910
lime	4151
chat	4205
lime	4225
lime & shale	4260
shale & lime	4437
lime	4456
shale & lime	4520
sand & shale	4535
shale & lime	4610
lime	4640

Tops	
Brown lime	3504
Lansing	3601
Base Kansas City	4014
Marmaton	4022
Mississippi	4152
Kinderhook	4240
Viola	4436
Simpson	4507
Sand	4529
Arbuckle	4610
T D	4640

DST 4149-58  
Open 1 hr. rec. 600' gas  
75' gas out and slightly oil  
out mud; trace of water.  
BHP #0 in 15 min.

Core: 4520-35 rec. 12' shaley  
sand 4520-25  
shale 4525-27  
Shaly sand: 4527-29  
sand 4529-35

**PLUGGING**  
FILE SEC. 32.721 R. 92  
BOOK PAGE 71 LINE 13

State of Kansas, County of Sedgwick  
I hereby certify that the above is a true and correct  
log of the Alexander #1 well, to the best of my  
knowledge and belief.

Dated at Wichita, Kansas, this 12th day of Jan. 1953.

RECEIVED  
STATE COMPTROLLER COMMISSION

JAN 13 1953

REGISTRATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me this 12th day of Jan. 1953

*James F. Raisten*  
James F. Raisten

*Elizabeth Ray*  
Notary Public

My commission expires Sept. 14, 1955