


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 21 Twp. 28 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Harms-Burt Drilling Co.
Lease Name Endicott Well No. 1
Office Address P.O. Box 184, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 7 19 60
Application for plugging filed September 7 19 60
Application for plugging approved September 7 (verbally) 19 60
Plugging commenced September 7 19 60
Plugging completed September 7 19 60
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	252'	8-5/8"	252'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from total depth to 240 ft. with plug and 15 sacks of cement at this point. Heavy mud to 35 ft. with a plug and 10 sacks of cement at this point.

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1960
CONSERVATION DIVISION
Wichita, Kansas

9-20-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms-Burt Drilling Co.
Address P.O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
P.O. Box 184, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of Sept, 1960

My commission expires 9-1-62
Fred W. Hampel Notary Public.

15-095-00133-0000

DRILLERS LOG

Company: Harms-Burt Drilling Company
Farm: Endicott #1
Commenced: August 23, 1960

NE NE NW Section 21-28-9W
Kingman County, Kansas
Completed: September 7, 1960

Elevation: 1645 KB

0-80	sand
80-252	red bed
252-450	red bed & shale
450-1075	shale - blue & gray
1075-1320	shale
1320-1460	shale & lime
1460-2040	lime
2040-2315	lime & shale
2315-2645	shale & lime
2645-2865	lime & shale
2865-2970	lime
2970-3075	lime & shale
3075-3270	lime
3270-3317	shale & lime
3317-3367	sand & shale
3367-3469	shale-sand-lime
3469-4061	lime
4061-4119	chert
4119-4137	lime
4137-4365	shale
4365-4416	Viola
4416-4450	Simpson

4450 Total Depth

Set 252 feet of 8-5/8 inch surface pipe. Cemented ^{with} 275 sacks of common cement and 2% calcium chloride.

Tops:	Heebner	3273'
	Brown Lime	3469'
	Lansing K.C.	3478'
	Mississippi	4061'
	Kinderhook	4134'
	Viola	4365'
	Simpson	4416'

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1960
CONSERVATION DIVISION
Wichita, Kansas

Drill Stem Test: #1 4063-4075 Open 1 hour. Shut in 15 minutes.
Recovered 31 feet of mud with spots of oil.
1BHP-145# FBHP-60#

#2 4075-4085' Open 1 1/2 hours. Shut in 20 minutes.
Recovered 170 feet of muddy salt water.
1BHP-1540# FBHP-1300#

Ran Electric Log.

Dry, plugged and abandoned.

Affidavit:
State of Kansas County of Barton ss

Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Allan Harms
P.O. Box 184, Great Bend, Kansas

Subscribed and Sworn to before me this 15th day of Sept., 1960

Notary Public

My commission expires 9-1-62

Fred H. Beach