

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-095-20407-000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 20 Twp. 28S Rge. 9 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
N/2 NW SE


Lease Owner Paxco, Inc.
Lease Name Swander Well No. 2
Office Address 245 South Terrace, Wichita, Ks. 67218
Character of Well (Completed as Oil, Gas or Dry Hole)
oil

Date Well completed March 4 19 76
Application for plugging filed Feb. 15 19 77
Application for plugging approved 19
Plugging commenced March 5 19 77
Plugging completed March 21 19 77
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jasper Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4499'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			312'	8 5/8"	312'	none
			4482'	4 1/2"	4482'	3338.36

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4385' and dumped 4 sacks of cement.

Set 10' rock bridge at 350'. Plugged well with 4 yards of ready mix cement.

RECEIVED
STATE OF KANSAS CORPORATION COMMISSION

MAR 24 1977

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1977

My commission expires

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Jenny Kasselmar
Notary Public.

DRILLERS WELL LOG

15-095-20407-0000

Date Commenced: February 20, 1976
 Date Completed: March 4, 1976

PAXCO, INC. (Operator)
 Aspen Drilling Co. (Contractor)
 SWANDER #2
 N/2 NW SE Sec. 20-T28S-R9W
 Kingman County, Kansas

Clay, Post Rock	40'
Sand, Red Bed & Shale	320'
Shale	900'
Shale & Red Bed	1413'
Shale	1440'
Shale & Shells	1660'
Shale	1830'
Shale & Lime	1980'
Lime & Shale	2110'
Shale	2355'
Lime & Shale	2615'
Broken Lime	2770'
Lime & Shale	3980'
Lime	4089'
Lime & Chert	4205'
Lime & Shale	4485'
Sand	4499'
T. D.	4499'

RECEIVED
 STATE CORPORATION COMMISSION

FEB 17 1977

CONSERVATION DIVISION
 Wichita, Kansas

Surface Casing: Set 8 jts. of 8 5/8" used casing at 312' w/225 sx. common cement - 2% calcium chloride & 2% gel.

DST #1 4122 - 4135'
 DST #2 4374 - 4402'


Set 109 jts. of 4 1/2" casing at 4482' w/125 sx. 18% salt pozmix. Plug down at 12:30 a.m. March 4, 1976.

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

William S. Schachle of lawful age, does hereby swear and state that the facts and statements contained herein are true and correct to the best of his knowledge.

William S. Schachle
 WILLIAM S. SCHACHLE

Subscribed and sworn to before me this 9th day of March, 1976.



My Commission Expires:
 December 30, 1978

Arlene Bailey
 Arlene Bailey - Notary Public