

15-095-21326-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kingman SEC. 20 TWP. 28S RGE. 9W E/W  
Location as in quarters or footage from lines:  
C N/2 NE SE


Lease Owner MTM Oil Company 532 5115  
Lease Name Sternacker Well No. 1  
Office Address RFD #1, Kingman, Kansas 67068  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed March 11, 1983  
Application for plugging filed March 15, 1983  
Plugging commenced March 11, 1983  
Plugging completed March 11, 1983  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Permission was obtained

Name of Conservation Agent who supervised plugging of this well Maurice Leslie, Medicine Lodge

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	339	24	7 jts. J-55	

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged well with 110 sks. com. 3%cc. 1st plug  
1400', 35 sks. 2nd plug 350'; 35 sks. 3rd plug  
40', 20 sks. 10 sks. - rathole, 5 sks. - mousehole  
5 sks. water well.

RECEIVED  
STATE CORPORATION COMMISSION

3-16-83 MAR 16 1983

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.

Pamalyn C. Allen (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Pamalyn C. Allen  
453 S. Webb Rd. P.O. Box 18611  
Wichita, (Address) Kansas 67207

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 83

Kathleen G. Quinn  
Kathleen G. Quinn Notary Public.

My Commission expires: \_\_\_\_\_



ALDEBARAN

453 SOUTH WEBB ROAD  
P.O. BOX 18611  
WICHITA, KANSAS 67207  
(316) 685-5372

WELL LOG

15-695-21326-0000



WELL NAME: Sternacker #1

WELL LOCATION: C N/2 NE SE

Sec. 20-28S-9W

OPERATOR: MTM Oil Company

COMMENCED: February 28, 1983

CONTRACTOR: Aldebaran Drilling Co., Inc.

COMPLETED: March 11, 1983

CASING RECORD: 8 5/8" set @  
339'.

FORMATION:

FROM:

TO:

Sand & Red Bed	0	580'
Red & Shale	580'	1370'
Shale	1370'	1634'
Lime & Shale	1634'	4100'
Mississippi	4100'	4201'
Kinderhook	4201'	4379'
Chelt shale, Sand & Dolomite, Viola	4379'	4436'
Simpson	4436'	4510'

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED  
C N/2 NE SE, Sec. 20-28S-9W TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 16 1983

ALDEBARAN DRILLING CO., INC.

CONSERVATION DIVISION  
Wichita, Kansas

*Pamelyn C. Allen*  
Pamelyn C. Allen, Accountant

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15 DAY OF March, 1983

MY APPOINTMENT EXPIRES:

KATHLEEN G. QUINN  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Appt. Exp. 3-20-83

*Kathleen G. Quinn*  
Kathleen G. Quinn  
NOTARY PUBLIC