

15-015-01533-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Call or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

KINGMAN County. Sec. 20 Twp. 28S Rge. 9 (E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines. NE-NE-SW
Lease Owner. Nebraska-Wyoming Oil Co.
Lease Name. Swander Well No. 2
Office Address. 524 University Bldg. Denver 2, Colorado
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
Date well completed. 6-20-48 19
Application for plugging filed. 6-20-48 19
Application for plugging approved. 6-20-48 19
Plugging commenced. 6-20-48 19
Plugging completed. 6-21-48 19
Reason for abandonment of well or producing formation.



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well. Mr. C. D. Stough
Producing formation. Depth to top. Bottom. Total Depth of Well. 4614 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pits gunned and heavy mud circulated with Drill Pipe on bottom.
Drove wood plug to 265', mixed and poured 15 sks. of cement through Drill Pipe.
Filled with heavy mud to 20' below bottom of cellar.
Drove wood plug and cemented to bottom of cellar.

6-25-48

STATE CORPORATION COMMISSION
JUN 25 1948

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to. Nebraska-Wyoming Oil Co.
Address. 524 University Bldg.
Denver 2, Colorado.

STATE OF KANSAS, COUNTY OF STAFFORD, SS. E. E. DUNCAN (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Duncan

STAFFORD, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 24 th day of JUNE, 19 48.

My commission expires Aug 4 - 1950

Notary Public.

21-6858-RS- 2-47-6M

PLUGGING
FILE SEC. 20 T. 28 S. R. 9 E.
BOOK PAGE LINE 5

PLAINS EXPLORATION COMPANY
 DRILLERS WELL LOG
 SWANDER WELL #2

15-095-0533-0000

Company - - Plains Exploration Co.
 Farm - - Swander # 2

Sec. 20- T. 28 - R. 9W
 Loc. NE-NE-SW

Total Depth - - 4614'
 Commenced - - 5-25-48 Completed - 6-21-48
 Shot or treated - None
 Contractor - Sterling Drilling Co.

County - Kingman
 Elev. - 1720 K.B.
 Prod. - Dry Hole

CASING RECORD

8 5/8" set at 281' cemented with 200 sks. 2% gel.

All measurements carried from Kelly Bushing

0' K. B.
 10' Bottom of cellar
 65' clay
 80' sand
 282' red bed
 750' red bed & shale
 1135' shale & shells
 1400' salt & shale
 1430' lime
 1570' lime & shale
 1585' sand
 1855' lime
 1985' lime & shale
 2145' lime
 2280' shale
 2290' lime
 3040' lime & shale
 3145' lime
 3215' shale & lime
 3420' lime
 3605' shale & lime
 3895' lime
 4125' lime & shale
 4135' lime
 4160' chat & chert
 4183' lime
 4220' shale & lime
 4411' shale
 4466' lime
 4492' shale
 4525' sand & shale
 4536' sand
 4550' shale
 4570' shale & dolomite
 4580' shale
 4614' lime
 T.D.

GEOLOGISTS TOPS

Lansing K. C.	3548'
Miss.	4122'
Viola	4411'
Simpson	4577'
Arbuckle	4580'

Fair porosity & saturation from 4123' to 4135'. Drill stem test- tool open 30 min. Gas to surface in 21 min. 60' of water & mud, possibly invasion water. No show of oil. Pressure in 12 min. went to 1550#.

Fair porosity, but no stain and no odor in top of viola, and electric log indicated water. Porosity, but no stain in arbuckle. D. A.

Lost circulation at 3380'.
 Slight mud loss at 3690'.

I HEREBY CERTIFY THE ABOVE RECORD IS A TRUE AND CORRECT RECORD OF THE
 DRILLERS LOG ON THIS WELL.

SIGNED

E. E. Duncan

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24 DAY OF June - 1948

MY COMMISSION EXPIRES Aug 4 - 1950

[Signature]
 NOTARY PUBLIC

JUN 25 1948

