

API NUMBER N/A 15-095-20307-000

LEASE NAME Hauser

WELL NUMBER 1

 Ft. from S Section Line

 NW -NE
 Ft. from E Section Line

SEC. 20 TWP. 28 RGE. 9W (E) or (W)

COUNTY Kingman

Date Well Completed N/A

Plugging Commenced 3-3-86

Plugging Completed 3-10-86

LEASE OPERATOR Frank J. Black

ADDRESS 600 W. Washington-McPherson, Ks. 67460

PHONE# (316) 241-2624 OPERATORS LICENSE NO. 5357

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District # 2

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation N/A Depth to Top Bottom T.D. 4469

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	286	8 5/8		
		0	4469	4 1/2		3183

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

F Fill with sand to 4000 ft. Dump 4 sxs. cement.

Pump top with 2 hulls, 12sxs. gel, & 60 sxs. Halliburton Light cement.

Max. Press. 500# -Shut in # 425

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address 420 5th. -Geneseo, Ks. 67444

STATE OF Kansas COUNTY OF Rice, ss.

Allen D. Nicholas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 86

Toni L. Prickett
Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires: Dec 25, 1988



3-13-86 MAR 13 1986

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING SUMMARY

Date 2-24-86 Time 0815 API Number 15-095-20307-6000

Who Called Alan Nicholas N/NE, Sec. 20, T 28 S, R 8 W/E

Phone No. _____ 4620 feet from N/8 section line

Directions _____ 1980 feet from W/8 section line

Lease Name Houser Well# 1

Operator: NCRA Lic# 5565 County Kinsman

Address Bx 6 Conductor Pipe: Size _____ Feet _____

Great Bend Ks. 67530 Surface Casing: Size 8 5/8 Feet 286

Well TD 4475 ft. TD formation _____

Production Pipe: Size 5 1/2 Feet 4469 Cement 1755X

Elevation _____ Anhydrite _____ Salt Member _____

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Plugging Contractor Nicholas Casings Pulling Lic # 6698 Tag# _____

Address Genesee Ks.

Company to plug at: Hour _____ Day: _____ Month: _____ Year: 19 _____

Current Operations T.A.

Perforations 4078-84 P.B.T.D. 4390 Perfs _____

Condition of well: No Prod. Bad Pipe _____ Bridged _____

Tubing in hole/pipe _____ Packer @ _____

Gas Zone _____ Hole taking/making fluid _____ Depth _____

Mud wt _____ Viscosity _____

Operations completed: Hour _____ Day _____ Month _____ Year 19 _____

VERBAL PLUGGING RECOMMENDATIONS Bottom sand to 4030 & 45Ks.

Top 3H 15 gel 110 8X

Actual Frank Black Bought for Salvage.

STATE CORPORATION COMMISSION

MAR 24 1986

CONSERVATION DIVISION
Wichita, Kansas

Cement Company _____ Ticket # _____


COMPANY **Donald T. Ingling**

SEC. 20 T. 28S R. 9W
LOG. NW NE

FARM **Hauser** NO. 1

TOTAL DEPTH **4,475'**
COMM. **December 6, 1973** COMP. **December 23, 1973**
SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED

COUNTY **Kingman**
KANSAS



CASING:
20 10
15 8 -5/8" 286' cemented w/225 lbs cement ELEVATION **1,682' KB**
12 6
13 5
4 1/2" 4,469' cemented w/175 lbs cement


Surface Soil and Clay	60'	LOG TOPS	
Sand and Gravel	80'	TARK	2544
Red Bed and Shale	286'	HOW	2778
Shale	1,375'	TOP	2890
Lime and Shale	1,490'	HEEB	3303
Lime	1,538'	DOUG	3340
Lime and Shale	3,073'	BR LM	3501
Chalk and Lime	3,225'	LANS	3511
Lime and Shale	3,610'	HUSH P	3840
Lime	3,710'	STARK	3870
Lime and Shale	4,097'	BKC	3934
Shale and Chert	4,110'	MISS LS	4075
Lime and Chert	4,173'	KH SH	4164
Lime and Shale	4,343'	VIOLA	4367
Lime, Chert and Shale	4,372'	LTD	4380
Lime and Shale	4,418'	RTD	4475
Lime and Sand	4,475'		
Rotary Total Depth	4,475'		

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } SS:



Subscribed and Sworn to before me a Notary Public in and for said county and state this 2nd. day of January, 1974.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1974

K. G. S. LIBRARY
RECEIVED
STATE CORPORATE COMMISSION
FEB 12 1975
CONSERVATION DIVISION
Wichita, Kansas