

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20,417-0000

LEASE NAME Hauser

WELL NUMBER #5

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 20 TWP 28 RGE. 9 (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 1-30-90

Plugging Completed 2-16-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Joe Amos (Kiwanda Energy)

ADDRESS 429 E. 56th South, Wichita, Ks. 67216

PHONE # (316) 522-2724 OPERATORS LICENSE NO. 09121

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 26, 1990 (date)

by Merlin Unruh (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	309'	None
				4-1/2"	4275'	3,137.10'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4025' and 5 sacks cement. Shot casing at 3500', 3000', 2800' and 2600'. Pulled 95 joints of 4-1/2" casing. B.J. Titan plugged well with 35 sacks cement at 1350', 35 sacks at 1000' and 110 sacks cement circulated to surface from 360'.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Amos

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

FEB 22 1990 2-22-90

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1990
CONSERVATION DIVISION
Wichita, Kansas

Jona M. Leatherman
Notary Public

My Commission Expires _____

