

Locate well correctly on above Section Plot

Kingman County, Sec. 35 Twp. 28 Rge. 6 (E) (W)
 Location as "NE/CNW/SW" or footage from lines C. E. L. NE/4 SE/4
 Lease Owner Hindman Oil & Gas Company
 Lease Name Fern Well No. 1
 Office Address No. 8 Hilltop, Hutchinson, Kansas 67501
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed March 8 1975
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 19
 Plugging completed March 8, 1975
 Reason for abandonment of well or producing formation Hole Dry

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	215'	8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 200' with 35 sacks of cement. Filled with mud to 40' & set plug with 15 sacks of cement. 2 sacks in rathole. Plug down at 11:30 A. M., March 8, 1975. Plugging completed by State Plugger, G. R. Biberstein, Attica, Kansas.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Blackstone Drilling, Inc.
 Address Box 455, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF Reno Rice
 Hindman Oil & Gas Company (Employer or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God, HINDMAN OIL & GAS COMPANY.

(Signature) BY: [Signature]
 No. 8 Hilltop, Hutchinson, Kansas 67501 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March 1975


[Signature]
 Zelpha Koch Notary Public



RECEIVED
 STATE CORPORATION COMMISSION

MAR 14 1975 3-14-75

CONSERVATION DIVISION
 Wichita, Kansas



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

March 10, 1975

15-095-20391-0000

COMPANY: HINDMAN OIL & GAS COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: RECEIVED STATE CORPORATION COMMISSION FERN #1
 LOCATION: C. EL. NE/4 SE/4, Sec. 35-28-6 Kingman County, Kansas
 COMMENCED: CONSERVATION DIVISION March 1, 1975
 (Wichita, Kansas)
 COMPLETED: March 8, 1975
 ELEVATION: 1442 K. B.

0	to	700	Shale
700	to	1115	Shale & Line
1115	to	1845	Line
1845	to	2125	Shale & Line
2125	to	2615	Line & Shale
2615	to	3075	Line
3075	to	3185	Shale & Line
3185	to	3695	Line
3695	to	3803	Line & Shale
3803	to	3109	Shale & Line
3109	to	3945	Mississippi
		3945	T. D.

Cut 12 1/2" hole to 215' and run 220' of 8 5/8 inch hole and cemented with 175 sacks of cement at 215'. Plug down at 12:30 P. M., March 1, 1975. Cut 7 7/8" hole to 3945'. Set bottom plug at 200' with 35 sacks of cement. Filled with mud to 40' and set plug with 15 sacks of cement. 2 sacks of cement in rat hole. Plugging completed at 11:30 A. M., March 8, 1975. Plugging completed by G. R. Biberstein, Attica, Kansas, State Plugger.

TOPS: MISSISSIPPI - 3109'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffa, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of your log on the Fern #1, located on the C. EL. NE/4 SE/4, Section 35-28-6, Kingman County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffa, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 10th day of March, 1975.


 Johnnie L. Schmidt - Notary Public

