

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman

County, Sec. 35 Twp. 28 Rge. (X) 6 (W)

Location as "NE/CNW4SW4" or footage from lines. Ctr. SE/4 SE/4
Lease Owner. Drillers Production Co., Inc.
Lease Name Lindt Well No. 1
Office Address 1020 Union National Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 13, 19 62
Application for plugging filed March 13, 19 62
Application for plugging approved March 13, 19 62
Plugging commenced March 13, 19 62
Plugging completed March 13, 19 62
Reason for abandonment of well or producing formation Non-Productive

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4020 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		2850		8-5/8"	212	None
Toronto		2861				
Douglas		2882				
B/Kansas City		3599				
Mississippi Chert		3930				
Mississippi Dolomite		3956				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole Full Drilling Mud 4020 to 200
Set Plug at 200' w/ 1 Sack of Hulls and
20 Sacks Cement. Set Plug at 40' w/
1/2 Sack of Hulls and 15 Sacks Cement.

RECEIVED

STATE CORPORATION COMMISSION

MAR 19 1962

CONSERVATION DIVISION

Wichita, Kansas

3-19-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Co., Inc.
Address 514 Orpheum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Bickford, Jr. (employee of owner) or

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Bickford, Jr.

1020 Union National Bldg., Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 62

My commission expires May 13, 1962

Harold H. Hunt
Notary Public.



15-095-0329-0000

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

LINDT #1
C SE SE SECTION 35-28S-6W
KINGMAN COUNTY, KANSAS

COMMENCED: 3-2-62
COMPLETED: 3-13-62

OPERATOR - DRILLER'S PRODUCTION CO., INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	214	RED BED	RAN 215' OF 8-5/8" CASING, SET @ 214' W/225 BAGS CEMENT.
214	370	RED BED	
370	1000	SHALE & SHELLS	
1000	1245	SHALE, SHELLS & LIME	
1245	1275	SHALE	
1275	1565	LIME	
1565	2965	LIME & SHALE	
2965	3140	SHALE & SAND	
3140	3455	SHALE & LIME	
3455	3605	LIME	
3605	3915	LIME & SHALE	
3915	3957	LIME, SHALE AND OCHERT	
3957	4020	LIME	
4020	TD		DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C SE SE SECTION 35-28S-6W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 15TH DAY OF MARCH, 1962, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

RECEIVED
STATE CORPORATE COMMISSION
MAR 19 1962
CONSERVATION DIVISION
Wichita, Kansas