


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 26 Twp. 28 Rge. 13 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

NE/NW/NW  
Lease Owner Continental Oil Company  
Lease Name Ed Brennan Well No. #2  
Office Address Box 267, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced October 12 19 77  
Plugging completed October 18 19 77  
Reason for abandonment of well or producing formation

depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well 4500'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	911'	none
				5 1/2"	4499'	2,226.99'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 2500' dumped 25' of sand and 5 sacks of cement.  
Shot pipe at 2250'.  
Pulled 63 joints 5 1/2" casing.  
Bailed hole down 350' and built 15' rock bridge, dumped 7 yards ready mix concrete.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 07 1977  
11-7-77  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.  
Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
Box 698 Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 4th day of November 1977

NOTARY PUBLIC  
KAREN M. MORTON  
Barton County, Kansas  
My Comm. Expires 1/17/1980

Karen M. Morton  
Notary Public.

CONTINENTAL OIL COMPANY - Operator

SIERRA PETROLEUM CO., INC. - Contractor

ED BREHM #2

T. D.: 4500'

NE NW NW

Sec. 26-28S-13W

Pratt County, Kansas

Commenced: 4-7-62

Completed: 4-23-62

Casing:

10-3/4" Set at 905'

5-1/2" Set at 4499'

Cement:

with 350 sx. cement

with 380 sx. cement

FORMATION

DEPTH

Surface Clay & Sand	90
Sand & Gravel	225
Red Bed	560
Shale & Shells	917
Shale	1080
Shale, Shells & Salt	1400
Shale & Shells	1860
Shale & Lime	3153
Lime	3255
Lime & Shale	3418
Lime	3655
Lime & Shale	3722
Lime	4378
Arbuckle	4500

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1977

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )

COUNTY OF RUSSELL )

ss:


I hereby certify that the above information is true and correct to best of my knowledge.

C. T. Honaker

Subscribed and sworn to before me this 27th day of April, 1962.

Leroy Dietz  
Notary Public

My commission expires: 10-17-63



State Corp. Comm.  
Kansas Geological Society  
CRW  
File