

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21.732⁰⁰⁻⁰⁰ (of this well). 6/89

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Knighton Oil Company, Inc. OPERATOR'S LICENSE NO. 5010

ADDRESS 710 Petroleum Building, Wichita, Ks. PHONE # (316) 264-7918
67202

LEASE (FARM) Huitt WELL NO. 1 WELL LOCATION SW SE NE COUNTY Pratt

SEC. 1 TWP. 28S RGE. 15 (E) (W) TOTAL DEPTH 4676 PLUG BACK TD 4600

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 411 CEMENTED WITH 400 SACKS

CASING SIZE 4 1/2" SET AT 4600 CEMENTED WITH 70 SACKS

PERFORATED AT 4531-37(2spf), 4507-17(4 spf), 4528-38(4 spf)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand to 50' above perfs, 4 sx cement on sand with
bailer. Pull Pipe. 400# hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100#
hulls, 8 5/8" wiper plug, 100 sx cement on top. All cement: 60/40 poz 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 20 April 89 8:00 AM.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Carl Gilpin PHONE # (913) 625-6702

ADDRESS 3403 Summer Lane, Hays, Kansas 67601

PLUGGING CONTRACTOR Pratt Well Service, Inc. LICENSE NO. 5893 6/89

ADDRESS P.O. Box 847, Pratt, Kansas 67124 PHONE # (316) 672-2531

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Carl M. Knighton Jr.
(Operator or Agent)

DATE: 18 April 89

RECEIVED
STATE CORPORATION COMMISSION
4-18-89
APR 18 1989
CONSERVATION DIVISION
Wichita, Kansas

①



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

THIS NOTICE
JUL 19 1989
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

April 19, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Knighton Oil Company, Inc.
710 Petroleum Building
Wichita, KS 67202

Huitt #1
SW SE NE
Sec. 01-28S-15W
Pratt County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760