

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-069-20,157-0000

LEASE NAME Reed

WELL NUMBER 1

NE NE NW
4,950 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 3 TWP. 29 RGE. 30W (X) or (W)

COUNTY Gray

Date Well Completed 10-30-82

Plugging Commenced 6-14-85

Plugging Completed 6-19-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ladd Petroleum

ADDRESS P. O. Box 2848, Tulsa, Oklahoma 74101

PHONE#(918) 587-6531 OPERATORS LICENSE NO. 6029

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Paul Luthi

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4190' Bottom 4202' T.D. 7350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1644	none
				5 1/2	5308	1854

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

CIBP@ 4380 Pump 30 sks. of cement @ 4204 to 3900

Pump 40 sks. of cement @ 1650

Pump 30 sks. of cement @ 660

Pump 15 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

David P. Spencer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David P. Spencer

(Address) David P. Spencer, Gen. Mgr. of Oper. P. O. Box 2848, Tulsa, Oklahoma 74101

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 85

RECEIVED
STATE CORPORATION COMMISSION
My Commission Expires: 1-23-89

Mary E. Russell
Notary Public

JUL 25 1985
7-25-85