

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-30091-0000

API NUMBER N/A

LEASE NAME E.W. Huitt

WELL NUMBER 1

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 14 TWP. 29S RGE. 33 (E) or (W)

COUNTY Haskell

Date Well Completed 6-7-66

Plugging Commenced 11-16-95

Plugging Completed 11-16-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 80201

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 6, 1995 (date)

by Steven Durant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached?

Producing Formation Lansing B
Kansas City B Depth to Top 4258' Bottom 4268' T.D. 5800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	689'	
	Production			5 1/2"	5535'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

See Attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. RECEIVED
KANSAS CORPORATION COMMISSION

Address 12-18-95

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company DEC 18 1995

STATE OF Colorado COUNTY OF Denver, ss.

CONSERVATION DIVISION
WICHITA, KS

Susan R. Potts (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 95

My Commission Expires: January 4, 1997

Notary Public

1070 BROADWAY
DENVER, CO 80201

October 6, 1995
To: Bill Chatham, Ulysses

Plugging and Abandonment Procedure
E. W. Huitt No. 1
Sec. 14 - T29S - R33W
Haskell, KS

*8 1/2" from
7710-H
Hew
Pump*

Refer to the attached wellbore diagram. Please plug and abandon this well using the following procedure:

1. MIRUSU. TOH w/ all rods x pump x tbq.
2. Spot 20 sx cement (i.e., 65/35 Poz mix 6% gel) across Kansas City "B" perms (4700'-4718').
3. Spot 20 sx cement (i.e., 65/35 Poz mix 6% gel) across Lansing "B" perms (4258'-4268').
4. Set cement retainer below the base of the Council Grove (see attached diagram); shoot squeeze holes and squeeze cement behind the 5-1/2" csg, across the Council Grove and Chase formations. Attempt to circulate cement to surface.
5. If cement can be circulated to surface in Step 5, follow by spotting 20 sx at 350' and 10 sx at 40' inside the 5-1/2" csg. If not, need to shoot squeeze holes at approximate location of TOC, and squeeze cement through remainder of 8-5/8" annulus, and backfill 5-1/2" with cement.
6. Cut off csg 6 ft below surface and cap.
7. Restore location.

Direct all questions to Greg Sanza (x5498) in Denver.

Guido

G. J. "Guido" Sanza
Engineer

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 18 1995

CONSERVATION DIVISION
WICHITA, KS

Proposed Wellbore Sketch

E. W. Huitt No. 1
 Amoco Production Company
 Section 14-T29S-R33W
 Haskell County, KS

GL = 2929'
 KB = 2938'



RECEIVED
 KANSAS CORPORATION COMMISSION

DEC 18 1995

CONSERVATION DIVISION
 WICHITA, KS