

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-081-20,748-0000

LEASE NAME Alleman

WELL NUMBER .1-2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4030 Ft. from S Section Line

1250 Ft. from E Section Line

SEC. 14 TWP. 29 RGE. 33 (E) or (W)

COUNTY Haskell

Date Well Completed 1-13-93

Plugging Commenced 12-21-93

Plugging Completed 12-21-93

LEASE OPERATOR Kansas Natural Gas, Inc.

ADDRESS P.O. Box 815 Sublette, KS 67877

PHONE# (316) 675-8185 OPERATORS LICENSE NO. 5269

Character of Well Hugoton - flooded zone

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-17-93 (date)

by Mr. Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Hugoton-Chase Depth to Top 2673' Bottom 2721' T.D. 2793'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Fresh water	650' 8 5/8" set at	727'	surf	8 5/8"	727'	0
	5 1/2" set at	2793'	surf	5 1/2"	2793'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Trip in hole 5 1/2" cement retainer plug and set at 2400'. Pump 50 sks Class "H" into perforations. Sting out of plug, pull tubing up hole to approx 1500', set 40 sk plug of 60/40 poz in anhydrite. Pull tubing up hole to approx 780', set 40 sks of 60/40 poz at base of surface pipe. Pull tubing up hole to 60' from G.L.,  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Cementing License No. \_\_\_\_\_  
Address P.O. Box 1598, Liberal, KS 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kansas Natural Gas, Inc.


STATE OF Kansas COUNTY OF Haskell, ss.

Steven M. Lehning (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steven M. Lehning  
(Address) P.O. Box 815, Sublette, KS 67877

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1993

My Commission Expires: September 11, 1996



SEE BACK  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1993  
12-22-93  
CONSERVATION DIVISION  
Wichita, Kansas