

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-081-00398-0000

API NUMBER Not Applicable

LEASE NAME Murphy

WELL NUMBER #1

2790 Ft. from S Section Line

3910 Ft. from E Section Line

SEC. 33 TWP. 29 RGE. 32 (E) or (W)

COUNTY Haskell

Date Well Completed 1-14-54

Plugging Commenced 3-10-93

Plugging Completed 3-10-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kansas Natural Gas, Inc.

ADDRESS P.O. Box 815, Sublette, KS 67877

PHONE# (316) 675-8185 OPERATORS LICENSE NO. 5269

Character of Well casing collapsed

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 9, 1993 (date)

by Mr. Steve Middleton, KCC, Dodge City, KS (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Chase Series Depth to Top 2664' Bottom 2750' T.D. 2754'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Fresh water 500'	10 3/4" set	519'	SURFACE	10 3/4"	519'	
Chase Series	7"	2754'	SURFACE	7"	2754'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Halliburton hooked onto surface pipe and had good cement to surface. Did not pump any on surface. Ran 2 7/8" tubing to 650' and pumped 100 sacks down 7" casing and good circulation back to surface. Cement was 35/65 Poz mix and 8% Gel. Cut well head off 6' below ground level and capped and leveled location.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Company License No. N/A

Address Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Steve Lehning, Kansas Natural Gas, Inc.

STATE OF Kansas COUNTY OF Haskell, ss.

Kansas Natural Gas, Inc. (Employee of Operator) Steve Lehning (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Steve Lehning

(Address) P.O. Box 815 Sublette, KS 67877

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 93

My Commission Expires: 9-11-96 Notary Public



RECEIVED
 STATE CORPORATION COMMISSION
 3-12-93
 MAR 12 1993
 CONSERVATION DIVISION
 Wichita, Kansas