

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-081-00047-0002  
API NUMBER \_\_\_\_\_

LEASE NAME Preedy Gas Unit

WELL NUMBER 1

SPOT LOCATION NW-SE

SEC. 33 TWP 29 RGE. 33 (X) or (W)

COUNTY Haskell

Date Well Completed 10-1961

Plugging Commenced 1-3-1989

Plugging Completed 1-6-1989

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Amoco Production Co.

ADDRESS Box 800, Denver Co. 80201

PHONE # (316) -649-2303 OPERATORS LICENSE NO. 5952

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing formation Kansas B Depth to top 4668 bottom 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	1852'	0'
Production				5 1/2"	5450	2050'

RECEIVED 545  
STATE CORPORATION COMMISSION  
1-12-89  
12 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Set CIBP at 4370' and dumped 2 sks. cement on bridge plug with baler - pump 45 sks. cement 1900' to 1800'  
Displace with mud to 600' - pump 90 sks. cement 600' to 400'  
Displace with mud to 40' - Put bridge and 10 sks. cement 40' to 5'  
Cut off 8 5/8", 5' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

Edgar J. Eves

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 6th day of Jan., 1989

Sandra L. Eves  
Notary Public

My Commission expires: 12-6-91

