

STATE OF KANSAS
STATE CORPORATION COMMISSION
260 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-00141-0000

API NUMBER Completed 1-15-45

LEASE NAME Wright J. B.

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-11

2540 Ft. from S Section Line

2540 Ft. from E Section Line

SEC. 11 TWP. 29S RGE. 34W (E) or (W)

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS One Mesa Square Box 2009 Amarillo, Tx. 79189-2009

COUNTY Haskell

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 5575

Date Well Completed 1-15-45

Character of Well D&A

Plugging Commenced 1-28-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-1-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Paul Luthi

Is ACO-1 filed? old well If not, is well log attached? Long sent w/Form CP-1 on 1-16-85

Producing Formation Chase Depth to Top 2502' Bottom 2541' T.D. 2743'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase	Gas	surface	660	10 3/4"	660'	3'
		surface	2543	7"	2543'	1020'
		2485'	2712'	5 1/2" Inr	227'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 40 sks. of cement @ 1020

Pump 50 sks. of cement @ 700 to 600

Put 20 sks. of cement @ 40 to 0 Cut off & cap 10 3/4 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service

License No. RECEIVED 6547

STATE CORPORATION COMMISSION

Address Box 506 Liberal, Kansas 67901

STATE OF Texas

COUNTY OF Potter, ss.

FEB 25 1985
2-25-85

G. Ed Richardson

(Employee of Operator Conservation Division of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) G. Ed Richardson

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 21 day of February, 19 85

Carolyn McKee
Notary Public

My Commission Expires: 9-16-85