

15-081-00142-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Haskell County, Sec. 11 Twp. 29S Rge. 34 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE/4 NE/4
Lease Owner Robert F. White
Lease Name Koenig "B" Well No. 1
Office Address 714 Union Center - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 7, 1963 1963
Application for plugging filed Oct. 7, 1963
Application for plugging approved _____ 19____
Plugging commenced Oct. 7 1963
Plugging completed Oct. 7 1963
Reason for abandonment of well or producing formation Not Productive

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production ---- 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation None Depth to top --- Bottom ---- Total Depth of Well 5430' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0	760'	8-5/8	760'	760' None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled with heavy drilling mud to 2760', Cemented with 100 sax cement. Filled with heavy drilling mud up to 760', cemented with 25 sax of cement. Filled to 40' and cemented with 15 sax. Filled to top of surface pipe and welded on cap.

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham - Michaelis Drilling Co. (Rotary Contractor)
Address Liberal, Kansas

STATE OF Kansas COUNTY OF Seward, ss.
Graham - Michaelis Drilling Company (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
Graham-Michaelis Drilling Company
(Signature) By [Signature]
Box 1294, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1963

My commission expires May 26, 1964 Frank R. Stubbins Notary Public.



KOEHNIG "B" #1

WELL RECORD:

LOCATION:

C NE NE Section 11-29S-34W
Haskell County, Kansas

Commenced: 9-18-63
Completed: 10-8-63
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Co.
Liberal Division
P. O. Box 1294
Liberal, Kansas

CASING RECORD:

20 Joints 8-5/8" 20# Casing
Cemented w/200 sx Common 2% cc.
2% Gel and w/250 sx Sunset

	<u>LOG</u>
Soil, Sand & Shale.	0 - 601
Sand & Red Bed	601 - 760
Shale, Red Bed & Sand	760 - 1870
Shale, Anhy & Lime	1870 - 2167
Lime & Shale	2167 - 3639
Chalky Lime	3639 - 3845
Lime & Shale	3845 - 4144
Lime	4144 - 4222
Lime & Shale	4222 - 4394
Lime	4394 - 4539
Lime & Shale	4539 - 4608
Lime	4608 - 4697
Lime & Shale	4697 - 4775
Lime	4775 - 4788
Lime & Shale	4788 - 4866
Lime	4866 - 4963
Lime & Shale	4963 - 5053
Lime	5053 - 5132
Lime & Shale	5132 - 5430

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964

CONSERVATION DIVISION
Wichita, Kansas

5430' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY
LIBERAL DIVISION

By H. R. Michaelis
H. R. Michaelis