


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Haskell County. Sec. 16 Twp. 29 Rge. 34 (EX) (W)



Location as "NE/CNW/SW" or footage from lines NW/SE  
Lease Owner Ashland Oil & Refining Company  
Lease Name L. E. Hickman Well No. 2  
Office Address ) P.O. Box 127 - Satanta, Kansas 67870  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 10, 1961 19  
Application for plugging filed May 26, 1966 19  
Application for plugging approved June 30, 1966 f 19  
Plugging commenced 7 - 18 19 66  
Plugging completed 7 - 20 19 66  
Reason for abandonment of well or producing formation Well will no longer produce commercially.  
If a producing well is abandoned, date of last production May 1, 1966  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edd Eves  
Producing formation Morrow Depth to top 5233 Bottom 5367 Total Depth of Well 5496 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1818	None
				5 1/2	5496	1990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mix 20 sacks cement to plug off perforations at 5342 feet.  
Stop plug at 5200 feet. Shoot pipe loose at 1990 feet. Stop pipe at 700 feet and pump 35 sacks cement at 700 to 600 feet. Lay pipe down and put 15 sacks cement at 45 feet to 0 feet. Use mud laden fluid between plugs.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

7-21-66

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargent's Casing Pulling Service  
Address Box 506 Liberal, Kansas

STATE OF Kansas COUNTY OF Haskell, ss.  
James H. Ipson (employee of owner) or (owner, or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James H. Ipson  
P.O. Box 127 - Satanta, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 66

My commission expires October 1, 1966  
H. J. Hughes Notary Public.

