


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 20 Twp 30 Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Eldorado Refining Company
Lease Name Wells Well No. 1
Office Address 306 Koch Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/2/ 19 55
Application for plugging filed 12:30 P.M. 2/2/ 19 55
Application for plugging approved 2/2/ 19 55
Plugging commenced 2/2/ 19 55
Plugging completed 2/2 19 55
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Seward W. Greider
Producing formation Depth to top Bottom Total Depth of Well 4352 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215	8 5/8	215	None
	No oil string was run					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 215', bridge hole
& cement with 25 sacks. Then heavy mud to
20 feet below cellar, bridge hole & cement with
10 sacks to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Picknell Drilling Company
Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts, Agent for Operator (under or over) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]
705 Fourth Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 55

[Signature] Notary Public.

My commission expires July 30, 1958

24-2675-S 2-52-20M
PLUGGING
FILE SEC 20 T 30 R 7W
BOX PAGE 95 LINE 5

2-19-55
CONSERVATION DIVISION
WICHITA, KANSAS

ROTARY DRILLING LOG

COMPANY: Eldorado Refining Company
Wichita, Kansas

Rotary Drilling Commenced 1/20/55

Rotary Drilling Completed 2/5/55

LOCATION: Wells #1 NE NE NE
20-30S-7W, Kingman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 215' (7 Jts) of 8 5/8" smls casing set with 150 sacks bulk cement circulated.

Filled with heavy mud to 215', bridge hole & cement with 25 sacks. Then heavy mud to 20' below cellar, bridge hole & cement with 10 sacks to bottom of cellar.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Red Rock	215	Circ. for samples @	4220
Red Bed	350		4241
Shale Shells	805		4255
Lime & shale	1435		4270
Lime	1700		4285
Lime & shale	2910		4295
Lime	3895		4315
Lime & shale	3967		4352
Lime	4218		
Shale & lime	4232		
Mississippi Lime	4352	RTD	

S.L.M. @ 1700' - O.K.
S.L.M. @ 4300' - O.K.

Slope Test @ 1700' 0° off
Slope Test @ 4300' 0° off

PLUGGING
FILE SEC 20 T 30 R 7W
PAGE 95 LINE 5

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
Attorney-in-Fact

STATE OF KANSAS, }
COUNTY OF SEDGWICK } ss.:

On this 18th day of February, 1955, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Harvey L. Steiner
Notary Public