

RECEIVED
STATE CORPORATION COMMISSION

12-26-72 DEC 26 1972

CONSERVATION DIVISION Form CP-4
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Kingman County, Sec 20 Twp. 30S Rge. (E) 7 (W)

Location as "NE/CNWKSWH" or footage from lines SW NW NW

Lease Owner Champlin Petroleum Company

Lease Name James G. Schuman Well No. 2

Office Address 2915 N. Lincoln, Oklahoma City, Okla. 73105

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 7-1 1956

Application for plugging filed 10-3 1972

Application for plugging approved 10-6 1972


Plugging commenced 10-26 1972

Plugging completed 11-6 1972

Reason for abandonment of well or producing formation depleted - not economical to operate

If a producing well is abandoned, date of last production 4-9 1969

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Biberstein

Producing formation Mississippi Depth to top 4218 Bottom 4228 Total Depth of Well 4376 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4218	4228	9 5/8"	260	None
				5 1/2"	4375	3622

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

checked hole to 4338, pushed plug to 4200', ran sand and 5 sacks of cement. Loaded hole with water, welded on 5 1/2" collar. Shot pipe at 3598', checked hole to 2910', couldn't get down. Pumped mud out of pipe, worked pipe loose and pulled 113 joints. Took head off and set 10' rock bridge at 260' and ran 6 yards ready-mix. Plugging completed on 11-6-72.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.

Address Chase, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

Harold E. Melvin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold E. Melvin

2915 N. Lincoln, Oklahoma City, Okla. 73105

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December 1972

OCT 8 1975

My commission expires _____

Notary Public

Handwritten mark

TO KANSAS CORPORATION COMMISSION
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

County Wichita SEC. 20 TWP. 30 RGE. 7 W

COMPANY OPERATING Champion Refining Company

OFFICE ADDRESS P. O. Box 552 - Enid, Oklahoma

FARM NAME James G. Schuman WELL NO. 2

WELL LOCATED 1/4 2/4 1/4

4290' EBL 330' F-L

CHARACTER OF WELL Oil

(640)

DRILLING COMMENCED May 29, 1956 DRILLING COMPLETED June 15, 1956

SIZE	WEIGHT	THDS	MAKE	FT.	AMOUNT PULLED	CEMENT
9 - 5/8	36	8	J-SMLS	260	None	200 plus 24 CaCl ₂
5 - 1/2	15.5	8	J-	4375.5	None	150
2 - 3/8	4.7	8	J-	4250.89		

FORMATION RECORD

	TOPS	BOTTOM	TOPS	BOTTOM
Red Rock	0	75		
Shale and Shells	75	262		
Red Bed and Shells	262	310		
Shale and Shells	310	962		
Anhydrite	962	978		
Shale and Shells	978	1255		
Shale and Lime	1255	1430		
Lime	1430	1585		
Lime and Shale	1585	3145		
Shale and Shells	3145	3250		
Shale and Lime	3250	3585		
Lime	3585	3625		
Lime and Shale	3625	3760		
Lime	3760	3875		
Shale and Lime	3875	4004		
Lime	4004	4050		
Shale and Lime	4050	4210		
Lime	4210	4284		
Lime and Chert	4284	4320		
Lime	4320	4375		
Total Depth	4375			

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 6 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to before me
 this 15 day of October, 1956
 My commission expires August 14, 1956

Superintendent
 Superintendent
 District Engineer
Notary Public
 Notary Public