

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Take Required Affidavit  
File or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kingman County, Sec. 20 Twp. 30S Rge. (A) 7 (W)

Location as "NE;CNW&SW" or footage from lines NW NW SE  
Lease Owner Mobil Oil Corporation  
Lease Name James G. Schuman Well No. 3  
Office Address P. O. Box 1934, Oklahoma City, Oklahoma 73101  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 1-1 1957  
Application for plugging filed 12-4 1973  
Application for plugging approved 12-6 1973  
Plugging commenced 9-21 1974  
Plugging completed 9-25 1974  
Reason for abandonment of well or producing formation Uneconomical to produce.



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation Mississippian Depth to top 4206 Bottom 4366 Total Depth of Well 4395 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian	Gas, Oil, Water	4210	4214	9-5/8	240	None
"	" " "	4247	4260	5 1/2	4394	3140

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back w/sand from 4366' - 4261'. Shot 5 1/2" casing at 3140' & recovered 5 1/2" casing from 3140'. Halliburton plugged well w/2 sacks hulls, 20 sacks gel mud & 100 sacks regular cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas

10-21-74

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Glenn Pipe Pulling  
Address 204 E. 6th, Ellinwood, Kansas 67526

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
Paul K. Langerberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul K. Langerberg  
Box 1934, Oklahoma City, Oklahoma 73101  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 1974

Richard M. Spurr  
Notary Public.

My commission expires 11-17-77

15-095-00863-0000

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS


*Handwritten initials*

COMPANY Magnolia Petroleum Co.  
FARM J. G. Schuman NO. 3

SEC. 20 T. 30S R. 7W  
LOC. NW NW SE

TOTAL DEPTH 4395  
COMM. 11/25/56 COMP. 1/1/57  
SHOT OR TREATED  
CONTRACTOR Graham-Michaelis Drlg.  
ISSUED

COUNTY Kingman



CASING

20 9 5/8" @ 240' w/250 sacks cem.  
15 8  
12 6  
13 5 1/2" @ 4394' & cem. w/200 sacks.

ELEVATION 1514 D.F.

PRODUCTION

P 8 B0 & 9 BWPD

FIGURES INDICATE BOTTOM OF FORMATIONS

Rathole 113  
Red bed 1230  
Red Bed, Shale, Anhydrite 1588  
Lime & Shale 4249  
Lime 4395

TOPS:

Lansing-Kansas City 3398  
Mississippian 4208  
Rotary Total Depth 4395  
Plug Back Depth 4366

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

DST #1, 4210-33, open 1 hr., fr blow, gas/63 min., rec. 45' SOCM, FP 37-78#, BHP 1578-1408# in 20 min.

DST #2, 4238-72, open 1 hr., fr blow, rec. 73' DM w/VSSO, FP 37 - 58#, BHP 585-117#/20 min. (pkr. slipped on FBHP).

DST #3, 4341-66, open 1 hr., vy wk blow, rec. 20' DM, FP 25-28#, BHP 37-37#/20"