

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	Sec. 20		

Locate well correctly on above
Section Plat

KINGMAN County. Sec. 20 Twp. 30S Rge. 7W (X) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner PETROLEUM, INC.,
Lease Name WELLS "1" Well No. 1
Office Address ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed APRIL 4 1964
Application for plugging filed APRIL 4 1964
Application for plugging approved APRIL 3 1964
Plugging commenced APRIL 3 1964
Plugging completed APRIL 4 1964
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING, PRATT, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 4320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDERED UP WITH HEAVY MUD TO 270, FOLLOWED BY A WOODEN PLUG AND 1/4 SACK HULLS.
PLACED 25 SACKS CEMENT ON TOP OF HULLS THRU DRILL PIPE. MUDDERED UP WITH HEAVY MUD
TO 40' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK HULLS. PLACED 10 SACKS ON TOP OF
HULLS TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

4-27-64

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD DIST. PROD. SUPT.

(Signature)

R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 22ND day of APRIL, 1964

My commission expires SEPTEMBER 23, 1967

Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 20 T. 30S R. 7W

FARM Wells

NO. I-1

LOC. SW SE NE

TOTAL DEPTH 4320'


COUNTY Kingman

COMM. 3-24-64

COMP. 4-4-64

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 255' w/200' SX



ELEVATION 1559' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

15' Surface Sand
 50' Red Rock
 600' Red Bed
 900' Shale and Shells
 1160' Shale and Lime
 1439' Lime and Shale
 1780' Lime
 2075' Lime and Shale
 2522' Shale and Lime Streaks
 2810' Shale and Lime
 3055' Shale
 3260' Shale and Lime
 4073' Lime
 4185' Lime and Shale
 4233' Lime
 4285' Lime and Shale
 4320' Lime and Chert
 4320' RTD

RECEIVED
 STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
 Wichita, Kansas

State of KansasCounty of Barton

SS

I, Sam N. Stephens of Garvey Drilling Companyupon oath state the above and foregoing is a true and correct copy of the log of the Wells I-1 well.Subscribed and sworn to before me this 16th day of April 19 64My Commission Expires: September 23rd, 1967

NOTARY PUBLIC