

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22-542-00-00

LEASE NAME Griffith

WELL NUMBER #12

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 30 TWP. 7 RGE. 17 (E) or (W)

COUNTY Boone

Date Well Completed 12/1/84

Plugging Commenced 8/30/00

Plugging Completed 9/1/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
offices within 30 days.

LEASE OPERATOR Black Diamond Oil

ADDRESS PO Box 641

PHONE/(785) 625-5891 OPERATORS LICENSE NO. 7076

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 8/14/00 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? Attached to well plugging app.

Producing Formation Arb. I-KC Topeka Depth to Top 2713 Bottom 3300 T.O. 3329

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil/Water	3246	TD	8 5/8	1234	0
I-KC	Oil/Water	3968	3194	5 1/2"	3327	2408'
Topeka	Oil/Water	2713	2924			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Sanded bottom. Sand at 2,648'. Boiled 5 sacks of Portland. Shot at 2,408'. Worked pipe 5" gain. pulled to 1,550'. Pumped 110 sacks and 3 huls. Pulled to 900'. Pumped 40 sacks 1 huls. Pulled to 450'. Circulated cement to surface with 95 sacks. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 E. Main St., Sterling, KS, 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Diamond Oil

STATE OF Kansas COUNTY OF Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 641



SWORN TO before me this 15th day of September, 2000

Verda M. Brin
Notary Public

My Commission Expires: 7-18-2003

