

1 051002

2-4-88

API NUMBER 15- 097-01,007-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SE, SEC. 35, T 29 S, R 18 W/E
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Nichols "H" Well # 1
County Kiowa 1166.08
Well Total Depth 5110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 4 Month: 2 Year: 19 88

Plugging proposal received from Jerry Collins

(company name) TXO Production Corporation (phone) 316-886-5605

were: 4 1/2" at 5109' Perfs at 4937-51, 4799-4804' Elevation 2174' GL

1st plug pump 1 sx hulls and 25 sx cement to bottom,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 4 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls, 25 sx cement to 4780',
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

2-9-88 FEB 09 1988

CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 300 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1369' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

Signed Richard W. Lacey (TECHNICIAN)

DATE 2-10-88

INV. NO. 19816