

1 030820

6-12-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 50' W C SE SW, SEC. 32, T 29 S, R 18 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,240-0000
660 feet from S section line
3350 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Parkin "F" Well # 2

Operator: TXO Production Corporation
Name &
Address 155 North Market, Suite 1000
Wichita, KS 67202

County Kiowa 161.04
Well Total Depth 4955 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 6 Year: 19 87

Plugging proposal received from Rick Davis

(company name) H-30, Inc. (phone) 316-793-3687

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1300-1400'

1st plug at 1290' with 50 sx cement, 2nd plug at 540' with 50 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2 a.m. Day: 12 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1290' with 50 sx cement,

2nd plug at 540' with 50 sx cement,

3rd plug at 270' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

6-19-87 JUN 19 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 4% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 6-22-87

INV. NO. 17298

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 27, 1987 month day year

API Number 15- 097-21,240-0000

OPERATOR: License # 5171 Name TXO Production Corp. Address 155 N. Market, Suite 1000 City/State/Zip Wichita, Kansas 67202 Contact Person Cory West Phone (316) 269-7655

50' W of C. SE. SW Sec. 32.. Twp. 29... S, Rg. 18... X West 660' Ft. from South Line of Section 3350' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107 Name H-30 B... Inc. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 660' feet County Kiowa Lease Name PARKIN "E" Well # 2 Ground surface elevation 22.00 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 100 Depth to bottom of usable water 200 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 250 Conductor pipe required no Projected Total Depth 5000 feet Formation Mississippi

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to RCC specifications. Date 5-26-87 Signature of Operator or Agent Cory West Title Drig. & Prod Engineer

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 11-26-87 Approved By 5-26-87

TXO called

50' W of C. SE. SW Sec. 32.. Twp. 29... S, Rg. 18... X East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

Table with 3 columns: Plug #, Depth (feet), and Material (Econolite). Rows include 1st plug @ 1200', 2nd plug @ 500', 3rd plug @ 280', 4th plug @ 40', 5th plug @, and (2) Rathole with.

Handwritten notes: PUSHER Rick Davis, TD 4955 FORMATION Pawnee, SURFACE PIPE 8 7/8 @ 263, ANHYDRITE ELEVATION, STARTING TIME & DATE 6-7-87 11:30 AM, COMPLETION TIME & DATE 2:00 AM 6-12-87, 1st PLUG @ 1290 FT. W/ 50 SX SX, 2nd PLUG @ 540 FT. W/ 50 IX SX, 3rd PLUG @ 270 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ W.W. Already done, CEMENT COMPANY, TECHNICIAN 6/4 for 4% B.J. Titman.

RECEIVED STATE CORPORATION COMMISSION JUN 19 1987 CONSERVATION DIVISION Wichita, Kansas