

1041342

TO: STATE CORPORATION COMMISSION **3-31**

API NUMBER 15-097-21,217-0000  
N/2 NE/4 SEC. 32, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

LEASE NAME NICHOLS "G" WELL # 2  
COUNTY KIOWA 159.58

OPERATOR LICENSE # 31925 5004 *Quality Well* WELL TOTAL DEPTH 4910 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4905' WITH 150 SX

NAME AND 125 N MARKET, SUITE 1075 SURFACE CASING: SIZE 8 5/8" @ 260' WITH 175 SX

ADDRESS WICHITA, KS 67202-1721

ABANDONED OIL WELL      GAS WELL X INPUT WELL      SWD WELL      D/A     

OTHER WELL AS HEREINAFTER INDICATED     

\* PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 EAST BETH DR., STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 30 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4797-4802

1ST PLUG SANDED BACK TO 4630' & PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

ON 3-30-99 WAS SHOT OFF @ 2620' AFTER SPOTTING FIRST PLUG- CASING HUNG UP. LOAD HOLE WITH

GEL & SPOTTED PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 1250' WITH 50 SX CEMENT- CASING HUNG

UP. ON 3-31-99 SHOT CASING BACK OFF FREE POINT (700'). PULLED CASING TO 310'- COULDN'T

CIRCULATE. PRESSURE UP DOWN HOLE. PULLED CASING TO 270'. 3RD PLUG AT 270' WITH 50 SX

CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART      NONE     

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 31 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT 1ST PLUG SANDED BACK TO 4630' & PUT 4 SX CEMENT ON TOP OF SAND

BRIDGE THRU BAILER. ON 3-30-99 WAS SHOT OFF AT 2620' AFTER SPOTTING FIRST PLUG-CASING

HUNG UP. LOAD HOLE WITH GEL AND SPOTTED PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 1250' WITH

50 SX CEMENT CASING HUNG UP. ON 3-31-99 SHOT CASING BACK OF FREE POINT (700'). PULLED

CASING TO 310'-COULDN'T CIRCULATE. PRESSURE UP DOWN HOLE. PULLED CASING TO 270'. 3RD PLUG

AT 270' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2170' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

**INVOICED**

SIGNED Steve Peter by SPM  
(TECHNICIAN) FORM CP-2/3

APR 8 1999  
4-8-99

DATE 4-9-99

CONSERVATION DIVISION  
Wichita, Kansas

WV 60813