

9-30

To: 1 090009
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION of S/2 N/2 SE, SEC. 20, T 29 S, R 32 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 081-20,653-0000
100' S & 30' E

1550 feet from S section line
1290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

Lease Name Holloway Well # 2-20
County Haskell 186.87
Well Total Depth 5750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1832

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO Inc. License Number 5147

Address 401 E. Douglas, #402, Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 30 Month: 9 Year: 19 90

Plugging proposal received from Kent Johnson

(company name) BEREDCO Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1780'
1st plug at 1860' with 80 sx cement, 2nd plug at 940' with 80 sx cement,
3rd plug at 470' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4 a.m. Day: 30 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1860' with 80 sx cement,

2nd plug at 940' with 80 sx cement,

3rd plug at 470' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1990 10-4-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-10-90

INV. NO. 29610

9-30

Signed [Signature]
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C.C. five (5) days prior to commencing well 5
Expected Spud Date 9/18/90 month day year SW NE SD Sec 20 Twp 29 S, Rg 32 East West

OPERATOR: License # 5363
Name: BEREXCO INC.
Address: 970 Fourth Financial Center
City/State/Zip: Wichita, Kansas 67202
Contact Person: Evan Mayhew
Phone: (316) 265-3311

CONTRACTOR: License #: 5147
Name: BEREDCO INC.

Well Drilled For: Well Class: Type Equipment:
 Oil ... inj ... Infield Mud Rotary
 Gas ... Storage Pool Ext. ... Air Rotary
... OMWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If ~~OMWO~~: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: _____

1650 1550 feet from South line of Section
990 1290 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)
County: Haskell
Lease Name: Holloway Well #: 2-20
Field Name: Unnamed
Is this a Prorated Field? ... yes no
Target Formation(s): Chester/Morrow
Nearest lease or unit boundary: 990-1290
Ground Surface Elevation: 2900 feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 445
Depth to bottom of usable water: 650
Surface Pipe by Alternate: 1 ... 2
Length of Surface Pipe Planned to be set: 1800
Length of Conductor pipe required: _____
Projected Total Depth: 5800
Formation at Total Depth: St. Louis
Water Source for Drilling Operations: ... well ... farm pond ... other
DWR Permit #: Applied for
Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

670' Alt. I Req.

Exp. 3/14/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,

Pusher Kent Johnson INIT. _____
SPUD DATE 9-19-90
LENGTH SURFACE PLANNED 1800'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 1832 CONDUCTOR _____
ANHYDRITE T- 1780 B- _____ ELEVATION _____
TD 5750 FORMATION Mis. S&P
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ SX Y N
Arbuckle Plug @ _____ Ft. W/ 80 SX
Hug./Council @ 1860 Ft. W/ 100 SX
Anhydrite Base @ _____ Ft. W/ _____ SX
1/2 Base Anyh. @ 940 Ft. W/ 80 SX
1/2, 1/2 Plug @ 470 Ft. W/ 40 SX
Bottom Surface @ 1860 Ft. W/ 80 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 14 SX
WATER WELL 14 SX (Arr. Well) Pond _____
Hauling _____
TECHNICIAN _____ DATE _____ RECEIVED _____
STATE _____ DIVISION _____
TYPE OF CEMENT 60/40 GR M/T _____
STARTING TIME 12:30 (AM/PM) DATE 9-19-90
COMPLETION TIME 4: _____ (AM/PM) DATE _____
CEMENT COMPANY Hall