

15-081-00376-0000

1-24

1 020204

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 N/2 SW, SEC. 13, T 29 S, R 32 W/4E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
2310 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5269
Operator: Kansas Natural Gas, Inc.
Name & Address: P.O. Box 818
Hays, KS 67601

Lease Name Boatright Well # 2
County Haskell 89.05
Well Total Depth 2740 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 565

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kansas Natural Gas, Inc. License Number 5269
Address P.O. Box 818, Hays, KS 67601

Company to plug at: Hour: 10:20 a.m. Day: 24 Month: 1 Year: 1989

Plugging proposal received from Steve Lehning
(company name) Kansas Natural Gas, Inc. (phone) 316-675-8175

were: 5 1/2" at 2720' PBTD 2720' Perfs at 2668-78', 2694-2708'

1st plug run 3 sx hulls with gel and 45 sx cement at 1828',

2nd plug run 55 sx cement at 1450',

3rd plug run 50 sx cement at 960',

4th plug 50 sx cement at 450, 5th plug at 40-0' with 15 sx cement,

6th plug pump 3 sx hulls and 90 sx cement down 8 5/8".
Plugging Proposal Received by Glenn D. Barber
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 24 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1836', tagged bottom, filled up with sand.

Tubing and rods in hole at 2246'. Hole in casing. Ran 3 sx hulls with gel and 45 sx cement at 1828', (60/40 Pozmix)

2nd plug pulled tubing to 1450', ran 55 sx cement, 3rd plug pulled tubing to 960', ran

50 sx cement, 4th plug pulled tubing to 450', ran 50 sx cement, 5th plug pulled tubing,

filled 5 1/2" to 0 with 15 sx cement, 6th plug pumped 3 sx hulls and 90 sx cement down 8 5/8".

Pressured to 320 psi. and common cement
Remarks: Used 60/40 Pozmix by Dowell Schlumberger. No casing recovery.

(If additional description is necessary, use BACK of this form.)
I (old / ~~new~~) observe this plugging.

INVOICED

DATE 2-3-89

INV. NO. 23852

1-24

MAY 16 1989

Signed Glenn D. Barber (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1989 2-1-89
CONSERVATION DIVISION
Glenn D. Barber
Wichita, Kansas
(TECHNICIAN)