

To: 1 051208
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-27 1889
API NUMBER 15- 081-20,526-0000
App. C NE, SEC. 13, T 29 S, R 32 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5269

4030 feet from S section line

1250 feet from E section line

Operator Name: Kansas Natural Gas, Inc.

Lease Name Boatright Well # 3

Address P.O. Box 818

County Haskell 89.44

Well Total Depth 2752 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 571

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kansas Natural Gas, Inc. License Number 5269

Address P.O. Box 818, Hays, KS 67601

Company to plug at: Hour: 11 a.m. Day: 27 Month: 9 Year: 19 89

Plugging proposal received from Steve Lehning

(company name) Kansas Natural Gas, Inc. (phone) 316-675-8175

were: 5 1/2" at 2737' PBTB 2750' Perfs at 2693-2703', 2712-2722'

1st plug at 2730' with 30 sx cement,

2nd plug at 1875' with 20 sx cement,

3rd plug at 580' with 20 sx cement,

4th plug at 30' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 27 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT All plugs through tubing:

1st plug at 2730' with 30 sx cement,

2nd plug at 1875' with 20 sx cement,

3rd plug at 580' with 20 sx cement,

4th plug at 30' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1989

10-5-89

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard M. Lutz
(TECHNICIAN)

DATE 10-9-89

INV. NO. 26052