

To: 1 051985
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-27

API NUMBER 15- Drilled in 1954
C SW, SEC. 11, T 29 S, R 32 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior, Inc.
Name: _____
Address P.O. Box 399
Garden City, KS 67846

Lease Name Howell Unit Well # 1
County Haskell 88.50
Well Total Depth 2723 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address: _____

Company to plug at: Hour: 8:30 a.m. Day: 27 Month: 11 Year: 1995

Plugging proposal received from Kevin Wiles

(company name) American Warrior, Inc. (phone) 316-275-2963

was: 5 1/2" at 2715', PBTD 2700', Perfs at 2650-90'

1st plug pump 200 lbs. hulls and 25 sx cement, displace to 2500'

2nd plug perforate at 700' attempt to circulate cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement, displaced to 2500'

2nd plug perforated at 700' and pumped 225 sx cement down 5 1/2". Did not gain circulation up 8 5/8".

3rd plug pumped 100 sx cement down 8 5/8" X 5 1/2" annulus.
Shut in pressure 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
DEC - 1 1995
CONSERVATION DIVISION
Wichita, Kansas

12-1-95

INVOICED (If additional description is necessary, use BACK of this form.)
I (did not observe) observe this plugging.

DATE 12-4-95

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 44174